

FORESTGATE SHIPBROKERS LIMITED



THE PROPOSED FORESTGATE - TOMARO CONTAINER TERMINAL PROJECT

FOR FORESTGATE SHIPBROKERS LIMITED









No.	Description	Date		E	Borag Limite	ed	PROJECT Tomaro Reclamation	CLIENT Forestgate	Shipbrokers I	Limi ^s Scale (ted (@ A3)
			ODE	STATUS	SUITABILITY DESCRIPTION	PURPOSE OF ISSUE	SHEET CONTENT PAGE	Issue Date Drawn by: Obaze – Adeslyun Checked by Checker	Project Number DRAWING NUMBER ZZ	1	REV





FORESTGATE - TOMARO ISLAND PROJECT DEVELOPMENT

Preliminary Design - Draft

BORAG (NIG.) LIMITED

FEBRUARY 2021



Borag Limited Toma ODE STATUS SUITABILITY DESCRIPTION PURPOSE OF ISSUE SHEET	CONTENT PAGE	A3)
--	--------------	-----





Introduction

Borag Nig. Limited was originally commissioned by Forestgate Shipbrokers Limited on the 31st October 2020 as Consultants and Project Supervisors for the reclamation of 18 hectares land area on Tomaro Island in Lagos State. As at this time, **M/s Telmarine Support Services Limited**, a Lagos based company had carried out preliminary studies and geotechnical investigations on the project.

Borag Nig. Limited studied the documents prepared by the above mentioned companies and came up with two Engineering Appraisals which were discussed in detail with representatives of MTBS at a meeting held in M/s Forestgate Shipbrokers Limited's office on Thursday 12th December 2020. It was agreed at this meeting that Borag Nig. Limited should design and prepare cost estimates for the reclamation phase

of the project based on our earlier submitted Engineering Appraisal of November 2020.

Our Preliminary Design derives from data gathered from the following:

- Numerous site visits.
- MTBS Initial Due Diligence Report of July 2020
- MTBS Technical Plan Draft of October 2020
- MTBS Technical Plan of December 2020
- Survey Plan from Nigerian Ports Authority commissioned Surveyor
- Bathymetric Survey Plan of the Middle Creek Channel from Nigerian Ports Authority
- Google Earth Imagery
- Our Engineering Appraisal of November 2020





The scope of works in this Preliminary Design and Cost Estimates include the following:

- Completion of De-rooting and site clearance works.
- Delineation and re-establishment of lost property beacons as allotted for 15 hectares.
- Acquisition dredging for materials required for the Hydraulic reclamation of the delineated property
- Geotechnical investigations after reclamation for soil integrity.
- Shore and property line protection and Jetty wall design studies

SCOPE OF WORKS.

1.0 DE-ROOTING AND SITE CLEARANCE

This item of work which was contracted to Messrs Laris Equipment (Nigeria) Limited is currently at about 80% completion as observed during a site inspection carried out on the 31st January 2021. Outstanding works on this aspect are the removal of roots, stumps and general clearing of the site. Tidal inundation of the site is observed to be 90% at high tide. Only one property beacon was found in place.

2.0 DELINEATION.

Proper delineation of the site boundaries for the re-establishment of property beacons (which were found missing) during the de-rooting exercise is to be carried out before the reclamation starts. This is to include the installation 5.8m length of GI posts finished with water based anti-rust paint, driven to a point depth of 2.3m and pegged at 60m intervals along the perimeter lines. *(See delineation drawings)*

Pre-reclamation survey, for the purpose of establishing the quantity and cost of sand filling, should follow at this stage.





3.0 DREDGING AND RECLAMATION.

A sand-fill thickness of 4.0m over the 19 ha site area will require approximately 760,000m3 of fill material. Please note that our design consideration is for a finished site level of 3.0m. The provision of an additional 1.0m to a total of 4.0m backfill is to allow for both bulking of sand and settlement. This is based on the rule of the thumb though still subject to our final empirical assertion.

According to the MTBS report, the channel area is a probable source for the sand to be used for this reclamation (for which a permit is required from NPA).

Assuming a channel width of 200m over the 600m frontage of the site, the depth of dredging required within the channel (to reclaim the site) will be about 6.5m.

Based on the indicated estimated production of approximately 51,500m3 of dredging per week [MTBS report of 4 December 2020 using the Client's dredger 1870 Dragon (CSD)], reclamation of the site by hydraulic means would require 24 weeks or about 6 months to complete.

Post-reclamation survey for the purpose of establishing the quantity of sand-filling to verify settlement and cost should follow. (Please see referral drawings for this stage)





4.0 SHORE, JETTY AND PROPERTY PROTECTION

Once full reclamation of the site has been achieved by sand-fill, the next thing will be to protect the integrity of the shoreline through installation of sheet piles.

Our design proposal is for a retaining wall type jetty (instead of the finger type which would lead to a reduction in channel width when a vessel is anchored). This makes great economical sense as the retaining wall acts as the jetty and provides protection to the shoreline at the same time.

Bearing in mind the 13.5m draught desired at the jetty and the indicative poor structure of the subsoil (from soil tests conducted so far), our design is for steel sheet piles as retaining wall with anchorage for its stability along the entire alignment of the shoreline.

Detailed design will be required to ascertain relevant information about the steel sheet piles e.g. size/section of sheet piles required, lengths of sheet piles, distance of anchor sheet pile behind the front sheet pile, tie-rod spacing, etc. This detailed design exercise can take place in parallel with the site hydraulic reclamation activity.

(See referral drawings included in this report)





5.0 METHODOLOGY FOR PROPERTY PERIMETER PROTECTION

It is preferable that the retaining wall be in place before dredging of the channel to the desired draught (13.5m) is carried out.

- Reclamation will commence along the shore line length (600m) with some space left for egress of water. This is to establish a work platform for geo-technical investigation survey activities to obtain the necessary parameters for the design of the retaining wall jetty which should be available almost at the inception of back-filling.
- The Sub-soil investigation should be commissioned within two weeks of the commencement of the sand-filling work.
- Geotechnical investigation over the entire site to determine relevant parameters that will be used in the design of both the retaining wall along the perimeter of the site and the piles for the structures proposed for the tank farm can be continued to completion in line the with the sand-filling for the rest of the site.
- The process for the procurement of sheet etc. should commence at about the same time with the sand-filling.

6.0 PROPOSAL FOR ADVANCE PROCUREMENT OF SHEET PILES

• An initial quantity of sheet piles can be estimated from design calculations based on the available soil report from Messrs **Telmarine Support Services**. With this information the steel manufacturers can commence production of a specific quantity which may be increased with the outcome of our proposed confirmatory geo-technical investigation. The effect of the confirmatory geo-technical investigations will help in concluding the final estimation of the total length of sheet piles required for the project. This process of advance procurement will help to save time.





SITE & ENVIRONMENTAL CONSIDERATIONS



SITE ALLOTMENT SURVEY

 PROPOSED FORESTGATE -TOMARO CONTAINER TERMINAL PROJECT

- GOOGLE IMAGERY STUDIES
- SITE OBSERVATIONS

No. Description Date Image: Status Image: Status SUITABILITY DESCRIPTION PURPOSE OF ISSUE	PROJECT Tomaro F SHEET CONTE	Reclamation ENT PAGE	CLIENT Forestgate Date Issue Date Drawn by: Obaze - Ades/yun Checked by Checker	Project number Project Number DRAWING NUMBER ZZ	Scale (@ A3)
---	---------------------------------------	-------------------------	--	--	--------------













	No.	Description	Date				-	PROJECT	CLIENT		
					F	Borag Limite	ed l	T D I U	Forestgate	Shipbrokers I	imited
								Tomaro Reclamation	Date	Project number	Scale (@ A3)
				ODE	STATUS	SUITABILITY DESCRIPTION	PURPOSE OF ISSUE	SHEET	Drawn by:	DRAWING NUMBER	REV
								CONTENT PAGE	Obaze – Adeslyun Checked by	77	
									Checker		

























PROPOSED DREDGING & RECLAMATION ACTIVITIES AT FORESTGATE FACILITY

FOR FORESTGATE SHIPBROKERS LIMITED





- 1. De-Rooting & Clearing
- 2. Delineation survey
- 3. Aquisition Dredging
- 4. Hydraulic Reclamation
- **5** Geotechnical Investigation
- 6 Shore & Property Line Protection
- 7. Pile Foundation Structures for the
- Proposed Forestgate Facilty

	No.	Description	Date		E	Borag Limite	ed	PROJECT Tomaro Reclamation	CLIENT Forestgate	Shipbrokers Project number	Limited Scale (@ A3)
				ODE	STATUS	SUITABILITY DESCRIPTION	PURPOSE OF ISSUE	SHEET CONTENT PAGE	Issue Date Drawn by: Obaze – Adeslyun Checked by Checker	Project Number DRAWING NUMBER ZZ	REV





DE-ROOTING AND SITE CLEARANCE CLIENT No. Description Date PROJECT **Borag Limited** Forestgate Shipbrokers Limited Tomaro Reclamation Scale (@ A3) Date Project number Issue Date Project Number STATUS SUITABILITY DESCRIPTION PURPOSE OF ISSUE ODE SHEET Drawn by: DRAWING NUMBER REV Obaze - Adesiyun CONTENT PAGE Checked by ZZ Checker





























DELINEATION WORKS CLIENT No. Description Date PROJECT **Borag Limited** Forestgate Shipbrokers Limited Tomaro Reclamation Scale (@ A3) Date Project number Issue Date Project Number STATUS SUITABILITY DESCRIPTION PURPOSE OF ISSUE ODE SHEET DRAWING NUMBER Drawn by: REV Obaze - Adesiyun CONTENT PAGE Checked by ZZ Checker

















ACQUISITION DREDGING AND

HYDRAULIC RECLAMATION WORKS







	No.	Description	Date		E	Borag Limite	ed	PROJECT Tomaro Reclamation		CLIENT Forestgate	Shipbrokers L Project number	.imi Scale	ted (@ A3)
				ODE	STATUS	SUITABILITY DESCRIPTION	PURPOSE OF ISSUE	SHEET CONTENT PAGE	-	Issue Date Drawn by: Obaze – Adeslyun Checked by Checker	Project Number DRAWING NUMBER ZZ		REV











RECLAMATION METHOD: -

SAND-FILLING TO START ALONG SHORE LINE AND BUILD A PLATFORM FOR CARRYING OUT GEOTECHNICAL INVESTIGATION ACTIVITES WITHIN 2 WEEKS





















CONTENT PAGE	Date Issue Date Drawn by: Obaze – Adeslyun Checked by	Project number Project Number DRAWING NUMBER ZZ	Scale (@ A3)
--------------	---	--	--------------

POST RECLAMATION WORKS CLIENT No. Description Date PROJECT **Borag Limited** Forestgate Shipbrokers Limited Tomaro Reclamation Scale (@ A3) Date Project number Issue Date Project Number STATUS SUITABILITY DESCRIPTION PURPOSE OF ISSUE ODE SHEET Drawn by: DRAWING NUMBER REV Obaze - Adesiyun CONTENT PAGE Checked by ZZ Checker

FORESTGATE – CONTAINER TERMINAL AT TOMARO ISLAND, LAGOS

7.0 CONCLUSION

This Preliminary Design and Cost Estimates are based on a land area of 15 hectares. The survey plan available to us is for 15 hectares. It is very important at this stage to resolve the true extent of the property to facilitate the delineation exercise which is key to the reclamation project.

BORAG NIG. LIMITED 9th February 2021